

# mm productions

*Performance Sound*

Unit 10 Smeaton Close  
Severalls Industrial Park  
Colchester  
Essex. CO4 9QY  
United Kingdom  
Telephone: +44 (0)1206 845947  
Facsimile: +44 (0)1206 853756  
E-mail: [inquiries@mmproductions.co.uk](mailto:inquiries@mmproductions.co.uk)  
Website: [www.mmproductions.co.uk](http://www.mmproductions.co.uk)

## **mm productions RISK ASSESSMENT**

Please find below a “general” risk assessment. An individual risk assessment applicable to a specific event is available on request.

### **Introduction**

This risk assessment is applicable to all work carried out by mm productions staff and any companies sub-contracted by them, on behalf of “The Client”. The work will consist of the installation and operation of Sound/PA systems.

### **Conduct of Work**

All mm productions staff and their sub-contractors will comply with “The Clients” site rules or their own rules if these are more stringent.

All work on site will be supervised by competent staff.

Any personal protective equipment (eg Hard hats), demanded for use on “The Clients” sites, will be provided to all staff by mm productions on request.

### **Main Hazards and Risks**

#### **Electrical Work**

All equipment in the installation will be powered from a source supplied by others. It is expected that a safety certificate will be available for this supply.

All electrical work by mm productions will comply with the requirements of the Electricity at Work Regulations 1989.

There will be no live working on site and no staff will be working on equipment having exposed live conductors.

All equipment will be PATs tested before being brought onto site and with prior notice certificates will be available for inspection.

All electrical work to be carried out by trained and competent staff.

The electrical installation in public areas will be supplied and certified by others.

The resulting risks from this work are considered to be insignificant.

#### **Working at Height**

Some installation work will require the use of ladders. Ladders will be supplied by either mm productions or “The Client” and where necessary a second person will always be available to foot the ladder.

All lifting operations will be carried out in accordance with the Lifting Operations and Lifting Equipment Regulations 1998 (LOLER).

Risks have been minimised by the use of competent staff.

#### **Slips & Trips**

All Slip & Trip hazards will be assessed fully by mm productions while on site, & if possible, equipment cables positioned to avoid crossing pedestrian routes.

Where this is not possible, precautions will be taken in the form of cable covers.

#### **Hazardous Substances**

No hazardous substances will be brought on site by mm productions staff.

Updated July 2006.

Martyn J Hunt - Director